

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24382-00-00
Spot: SEWNWE Sec/Twnshp/Rge: 16-16S-13W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DEUTSCH Well #: 2
County: BARTON Total Vertical Depth: 3389 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	524	0	60/40 POZ 195 SX
PROD	5.5	3381	2210	110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2010 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE, PRODUCTI Company: DAYSTAR PETROLEUM, INC. Phone: (620) 793-2757

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.
Cut and pulled 2210' casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2010 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Sanded off bottom and topped with 5 sxs cement.
Cut and pulled 2210' casing.
Pulled up to 1500' - pumped 130 sxs cement with 300# hulls.
Pulled to 850' - pumped 40 sxs cement with 100# hulls.
Pulled to 525' - pumped 60 sxs cement.
Pulled to 150' - circulated with 45 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
3387	3389		
3381	3387		

INVOICED
DATE _____
INV. NO. _____

Remarks: COPELAND ACID AND CEMENTING-TICKET #33744.

Plugged through: CSG

District: 04

Signed Marvin Mills
(TECHNICIAN) CM

AUG 23 2010

RECEIVED Form CP-2/3
AUG 26 2010
KCC WICHITA

WOODMAN-IANNITTI OIL COMPANY
GREAT BEND, KS 67530

16-16 -13W
75'W, C SE NW NE

#2 DEUTSCH

site: 9-1/4 N OF HOISINGTON, KS city: BARTON
contr: WOODMAN-IANNITTI DRILLING COMPANY field: TRAPP
geol: TODD MORGENSTERN

API 15-009-24382

fr date 07/24/89 spd date 07/28/89 drlg comp 08/01/89 card issued 10/04/89 last revised 10/04/89

ELV: 1926 KB SMP	
tops.....depth/datum	
ANH.....863 +1063	
B/ANH.....892 +1034	
HEEB.....3049 -1123	
TOR.....3081 -1155	
BR LM.....3131 -1205	
LANS.....3141 -1215	
BKC.....3362 -1436	
ARB.....3378 -1452	
RTD.....3382 -1456	
DDTD.....3389 -1463	
NO LOG	

IP status:
OIL, P 15 BO & 3 BWPD, ARB 3381-3389 ,
NOTE: CORRECTION: 8/9/89 - ORIG FR IN SE NW NE
CSG: 8-5/8" 523.7 / 195 SX, 5-1/2" 3381 / 100 SX
NO CORES
DST (1) 3362-3382 (ARB), / 45-45-45-45, (1ST OP) WB
BLDG TO FB, (2ND OP) VWB, REC 220' CLEAN GSY OIL
ISIP 943# FSIP 896# IFP 35# -58# FFP 70# -94# IHP
1738# FHP 1738#
MICT - CO TO 3382, DD 3387, (ARB OH), AC 250 GAL
(15% NE), SO, DD 3389, AC 200 GAL (28% FE), SO, SET
2-7/8" TBG AT 3380, NO PKR, POP, P 15 BO & 3 BWPD
(GR 36), 8/26/89

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS