

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-04179-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 4-18S-8W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: HAWKINS Well #: 2  
County: RICE Total Vertical Depth: 3219 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		
PROD	5.5	3211		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE BODINE, PRODUCTI Company: \_\_\_\_\_ Phone: (620) 792-6702

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/10/2010 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, CK BOTTOM. SAND PERFS TO 3150' & CAP WITH 5 SX'S CEMENT.  
PERFORATE @ 1150', 800' & 270'. RUN TUBING TO 1150' & PUMP 35 SX'S CEMENT,  
PULL TUBING TO 800' PUMP 35 SXS CEMENT, PULL TUBING TO 270' & CIRCULATE  
CEMENT TO SURFACE. PULL TUBING OUT & TOP OFF.

**INVOICED**

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #6236. COPELAND CEMENT #C-35105.

Plugged through: TBG

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

RECEIVED  
SEP 23 2010  
9-23-10  
KCC WICHITA

Form CP-2/3