

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21361-00-00
Spot: E2SWNE Sec/Twnshp/Rge: 30-18S-7W
3300 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PEVERLEY Well #: 2
County: RICE Total Vertical Depth: 3250 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 SX
PROD	5.5	3249		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2010 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL
Date/Time Plugging Completed: 09/13/2010 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND TO 3140' & CAP WITH 5 SX'S CEMENT. PERFORATE @ 1050', 700', & 275'. RUN TUBING TO 1050' & PUMP 35 SX'S CEMENT, PULL TUBING TO 700' & PUMP 35 SX'S CEMENT, PULL TUBING TO 275' & CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT & TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3190	3200		ARBUCKLE PERFS

INVOICED

DATE _____

INV. NO. _____

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS. #6238. COPELAND TICKET #C-35109.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED

SEP 23 2010
9-23-10
KCC WICHITA

Form CP-2/3