

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23014-00-00  
Spot: NENENW Sec/Twnshp/Rge: 13-16S-14W  
330 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: SAUSEN Well #: 1  
County: BARTON Total Vertical Depth: 3333 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	248	0	165 SX
PROD	5.5	3330	0	125 AZ

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2010 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM, INC. Phone: (620) 793-2757

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 10 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/26/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1500' - 800' - 450' - 150'.  
Ran tubing to 3268' - pumped 10 sxs gel - followed with 90 sxs cement.  
Pulled tubing to 1550' - pumped 90 sxs cement.  
Pulled tubing to 800' - pumped 40 sxs cement.  
Pulled tubing to 500' - circulated to surface with 140 sxs cement.  
Pulled tubing - tied to surface pipe and pumped 5 sxs cement. Shut in.

Perfs:

Top	Bot	Thru	Comments
3330	3333		ARBUCKLE

**INVOICED**  
DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

Remarks: COPELAND ACID AND CEMENTING COMPANY.  
Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICAL) **RECEIVED** CM

**AUG 30 2010**  
**KCC WICHITA**

Form CP-2/3

**AUG 27 2010**

NATIONAL DEVELOPMENT COMPANY  
833 NORTH WACO

#1 SAUSEN

13-16-14W  
NE NE NW

WICHITA, KS 67530


CONTR DUKE DRG. CO., INC. CTY BARTON

GEOL \_\_\_\_\_ FIELD TRAPP

ELV 1918 KB SPD 1/6/83 CARD ISSUED 6/23/83 IP P 52 BOPD & 2% WTR

API 15-009-23,014

ARB OH 3330-3333



SMP	Tops .....	Depth/Datum	
			8 5/8 " 248; 5 1/2 " 3330
TOP	.....	2810- 892	DST (1) 3130-65 (LANS) / 30-30-30-30, REC 90' W, SIP 302-292#, FP 52-73#
HEEB	.....	3037-1119	DST (2) 3303-32 (LANS, ARB) / 30-30-30-30, 100' GIP, REC 20' O & GCM, 180' HO & GCM, SIP 873-863#, FP 52/94
TOR	.....	3055-1137	MICT - CO, (ARB OH), AC 250G, SWB DWN, GSO, POP, P 52 BOPD & 2% WTR, 1/22/83
DOUG	.....	3068-1150	
BR LM	.....	3105-1187	
LANS	.....	3118-1200	
ARB	.....	3329-1411	
RTD	.....	3333-1415	

INDEPENDENT OIL & GAS SERVICE