

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21370-00-00
Spot: SWNESW Sec/Twnshp/Rge: 7-10S-22W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: TURNER Well #: 2
County: GRAHAM Total Vertical Depth: 4220 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204	0	125 SX
PROD	4.5	4203	0	600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2010 9:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: BRET HILDEBRAND Company: DNR OIL & GAS, INC. Phone: (720) 871-7311

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.
Tubing stuck in the hole at 1400'.
Perforated at 1250' and 255'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2010 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1390' - pumped 60 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked to 4 1/2" casing. Squeezed with 100 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 900#. S.I.P. 250#.
Hooked to 8 5/8" x 4 1/2" annulus - pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
4076	4084		

INVOICED

DATE _____
INSTR. NO. _____

Remarks: ALLIED CEMENTING COMPANY-TICKET 335142A.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

NOV 17 2010

Form CP-2/3

KCC WICHITA

NOV 12 2010