

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21861-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 32-14S-29W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: THOMPSON-COBERLY Well #: 3
County: GOVE Total Vertical Depth: 4308 feet

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W 47TH ST STE 318
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/13/2010 2:00 PM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: MARK Company: DOUBLE EAGLE EXPLORATION, I Phone: (816) 531-0202

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 08/13/2010 3:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 2025' w/25 sxs.
2nd. Plug at 1020' w/100 sxs.
3rd. Plug at 315' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

INVOICED

DATE _____
INV. NO. _____

Remarks: CONSOLIDATED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Basye
(TECHNICIAN)

CM

RECEIVED

AUG 26 2010

Form CP-2/3

AUG 24 2010

KCC WICHITA