

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25114-00-00
Spot: NESESWSW Sec/Twnshp/Rge: 2-18S-21W
450 feet from S Section Line, 1130 feet from W Section Line
Lease Name: KLEWENO Well #: 1-2
County: NESS Total Vertical Depth: 4290 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1156		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/04/2010 7:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 50 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 10/04/2010 10:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

1ST PLUG AT 1440' WITH 40 SX CMT. 2ND PLUG AT 1170' WITH 50 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
OCT - 8 2010
KCC DODGE CITY

RECEIVED
OCT 14 2010
KCC WICHITA

Form CP-2/3