

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-33166-00-00
Spot: E2SWSE Sec/Twnshp/Rge: 15-13S-21W
660 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MUHLHEIM B Well #: 2
County: TREGO Total Vertical Depth: 3900 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 231 | 0 | 150 SX |
| DVT | | 1603 | | |
| PROD | 5.5 | 3894 | 0 | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2010 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO, INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel.
DV Tool at 1603'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2010 10:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped 75 sxs cement with 300# hulls - followed with 16 sxs gel - followed with 185 sxs cement and 300# hulls.
Max. P.S.I. 500#. S.I.P. 250#.
Tied onto backside - pumped 10 sxs cement.
Shut in 200# P.S.I.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3894 | 3900 | | |
| 3856 | 3860 | | |
| 3840 | 3844 | | |
| 3827 | 3830 | | |
| 3732 | 3740 | | |
| 3670 | 3676 | | |
| 3610 | 3616 | | |
| 3594 | 3600 | | |
| 3548 | 3562 | | |

DATE _____
INV. NO. _____

RECEIVED
AUG 06 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4205.

KCC WICHITA

Plugged through: CSG

District: 04

Signed Marvin Mills
(TECHNICIAN)

CM

AUG 03 2010

BIRMINGHAM-BARTLETT DRLG. #2 MUHLHEIM 'B' 15-13-21W
E2 SW SE

Contr. COMPANY TOOLS TREGO County

E 2233RB Comm. 3/21/63 Comp. 4/25/63 IP PMP 79 BOPD + 2% WTR
ARB 3894-3901

| LOG Tops | Depth | Datum |
|----------|-------|-------|
| ANH | 1591 | +642 |
| HEEB | 3478 | -1245 |
| TOR | 3496 | -1263 |
| LANS | 3514 | -1281 |
| MARM | 3827 | -1594 |
| ARB | 3892 | -1659 |
| TD | 3901 | -1668 |


Casing

8" 231/170 sx:
5" 3894:

DST 3506-30/30", 20' M, BHP 455-134#/20", FP 0-0#:
DST 3534-60/1 HR, 600' GIP, 250' HOCM, 60' MO, BHP 1179-1119#/20", FP 37-111#:

DD 3901: FU 1500' OIL/12 HRS: A
500: SWB 5 BOPH/4 HRS: POP:

MUHLHEIM



GEOL-JACK CHILDERS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS