

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21191-00-00
Spot: NESWNWSW Sec/Twnshp/Rge: 5-22S-4E
1717 feet from S Section Line, 4730 feet from E Section Line
Lease Name: LATHROP-HAWK A Well #: 3
County: MARION Total Vertical Depth: 2350 feet

Operator License No.: 6131
Op Name: DRILLERS & PRODUCERS, INC.
Address: PO BOX 385
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 SX
PROD	4.5	2349	992	50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____

Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2010 2:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

9/17/2010 PHILLIPS RAN TUBING INTO 2304'. CONSOLIDATED TIED ON BROKE CIRCULATION AND THEN PUMPED A 35 SXS PLUG OF 60/40 POS W/4% GEL, 4% CAC1 AND 1SX FLOW SEAL. PHILLIPS PULLED TUBING AND TIED ON TO PULL STRETCH IN 4.5". CONSOLIDATED RAN WIRE LINE DOWN AND TAGGED PLUG @ 1944' DYNALOG OUT AND SHOT OFF CASING @ 992'. PHILLIPS PULLED 4.5" AND THEN RAN 290' OF 2" BACK IN THE HOLE. CONSOLIDATED TIED ON AND BROKE CIRCULATION. CONSOLIDATED THEN PUMPED CEMENT AND CIRCULATED IT TO SURFACE. PHILLIPS PULLED TUBING AND CONSOLIDATED TOPPED OFF THE WELL. CONSOLIDATED USED 130 SXS 60/40 POS W/4% GEL ON THE TOP PLUG. THEY FINISHED AROUND 2:00PM. THEY USED A TOTL OF 165 SXS 60/40 POS W/4% GEL TK #28510. 9/21/2010 I CHECKED TOP PLUG FINDING IT DOWN ABOUT 7'. I TALKED WITH DRILLERS & PRODUCERS. THEY WILL TOP OFF BEFORE COVERING UP PITS.

Perfs:

Top	Bot	Thru	Comments
2320	2330	CSG	

INVOICED

DATE _____

INV. NO. _____

RECEIVED

OCT 01 2010

KCC WICHITA

Remarks: WELL HAD A DENIED TA

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)