

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21024-00-00
Spot: NWENWSE Sec/Twnshp/Rge: 5-22S-4E
2539 feet from S Section Line, 1805 feet from E Section Line
Lease Name: LATHROP-HAWK Well #: 7-C
County: MARION Total Vertical Depth: 2525 feet

Operator License No.: 6131
Op Name: DRILLERS & PRODUCERS, INC.
Address: PO BOX 385
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		
PROD	5.5	2523		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2010 9:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BILL HANSON Company: DRILLERS & PRODUCERS Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/03/2010 3:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

6/3/2010 PHILLIPS RAN 2 7/8" TUBING TO 2468', AND CONSOLIDATED PUMPED 35 SXS PLUG USING 60/40 POS W/4% GEL & 3%CC. PHILLIPS PULLED TUBING. CONSOLIDATED RAN DOWN WITH WIRE LINE AND TAGGED PLUG @ 2260'. PHILLIPS PULLED STRETCH IN 5 1/2" AND DYNALOG SHOT CASING @ 250'. PHILLIPS PULLED 90 THOUSAND AND COULD NOT PULL CASING FREE. BILL CALLED AND SPOKE TO ME ABOUT RUNNING 1" DOWN BACKSIDE. I AGREED THIS WAS PROBABLY THE BEST OPTION. PHILLIPS RAN 1" DOWN BACKSIDE AND TAG SOLID @ 110'. THEY THEN RAN 2 7/8" DOWN 5 1/2" TO 270'. CONSOLIDATED TIED ON AND PUMPED 35 SXS DOWN 1" CIRCULATING IT TO SURFACE. THEY THEN TIED ON TO THE 2 7/8" AND CIRCULATED 71 SXS FROM 270' TO SURFACE. CONSOLIDATED USED A TOTAL 141 SXS 60/40 POS W/4% GEL TK #28474. 6/4/2010 I CHECKED TOP PLUG FINDING IT DOWN 18'. I TALKED WITH BIL H. & BILL R. THEY ARE ON THEIR WAY TO DRY SACK WELL TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2492			CSG

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

OCT 15 2010

KCC WICHITA