

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-30517-00-01  
Spot: NENWSE Sec/Twnshp/Rge: 7-15S-13W  
2310 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: MAAG Well #: 3  
County: RUSSELL Total Vertical Depth: 3293 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	440	0	w/unknown sxs cmt
PROD	5.5	3291	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2010 9:00 AM  
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE  
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Old well has not produced since 1993. Casing separated at 900' - could not get tools through. Drilled and milled on spot for a day and a half. Will plug from there. Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls. Perfed at 850'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/30/2010 11:00 AM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Ran tubing to 840' - pumped 200 sxs cement with zero hulls.  
Pumped 50 sxs cement - circulated to surface.  
Pulled tubing - tied onto casing - pumped 25 sxs cement - cement circulated out surface pipe.  
Shut in at 300# P.S.I.

**Perfs:**

Top	Bot	Thru	Comments
3285	3293		ARBUCKLE
3228	3234		LKC
3187	3191		LKC
3152	3158		LKC
3081	3084		LKC
3037	3043		LKC
3019	3023		LKC

**INVOICED**

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_

**RECEIVED**

**AUG 04 2010**

**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

**AUG 02 2010**

LIVINGSTON OIL CO.

#3 MAAG (OWWO)

7-15-13W  
NE NW SE

Contr. RED TIGER DRLG

RUSSELL

County

E 1825 KB Comm.

Comp. 7/28/66

IP PMP 20 BO + 30 BWPD  
(LANS 3019-84)


LOG Tops	Depth	Datum
*ANH	815	+1010
*TOP	2700	-875
*HEEB	2947	-1122
LANS	2999	-1174
*SHLY CONG	3270	-1445
ARB	3281	-1456
TD	3293	-1468

Casing  
8" 440

WAS; GREAT LAKES CARBON CORP  
#3 MAAG, D & A, 1/16/46  
DST 3039-52/45", 40' M,  
STN @ 3098-3116; 3196-3202:

NEW INFO: CO 3293 RTD; 5" 3290/150  
SX; 12/3081-84; 24/3037-43;  
PF 16/3019-23; A 3750; SWB  
3 1/2 BFPH, 20% OIL;

TRAPP



\* OLD SMP TOPS  
INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS