

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22694-00-00
Spot: W2NENESE Sec/Twnshp/Rge: 25-32S-37W
2310 feet from S Section Line, 500 feet from E Section Line
Lease Name: BOND Well #: 25 #1
County: STEVENS Total Vertical Depth: 6600 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4535		WITH 5 SX CMT
CIBP		4910		
SURF	8.625	1691		WITH 500 SX CMT
PROD	4.5	5299	2506	WITH 140 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/10/2010 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4535' WITH 2 SX CMT. PLUG AT 1741' WITH 120 SX CMT. PLUG AT 630' WITH 60 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2010 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 4535' WITH 5 SX CMT. 1ST PLUG AT 1740' WITH 120 SX CMT. 2ND PLUG AT 630' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4972	4983		LANSING
4585	4592		LANSING

INVOICED

DATE _____

INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
AUG 11 2010
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

AUG 19 2010

KCC WICHITA

Form CP-20