

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22755-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 26-31S-39W
640 feet from S Section Line, 1685 feet from E Section Line
Lease Name: CENTRAL PLAINS Well #: 26 #1
County: STEVENS Total Vertical Depth: 6200 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1733		WITH 500 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/05/2010 5:00 AM
Plug Co. License No.: 34000 Plug Co. Name: KENAI MID-CONTINENT, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 1750' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 10/05/2010 7:03 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

Perfs:

1ST PLUG AT 1750' WITH 100 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GE L BY HALLIBURTON.

Plugged through: DP

District: 01

RECEIVED
OCT - 8 2010
KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN) RECEIVED

OCT 14 2010 Form CP-2/3
KCC WICHITA ✓