

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-22074-01-00
Spot: N2SESENW Sec/Twnshp/Rge: 14-34S-34W
2220 feet from N Section Line, 2310 feet from W Section Line
Lease Name: CHARLES Well #: 14 1H
County: SEWARD Total Vertical Depth: 8000 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5502		WITH 5 SX CMT
SURF	9.625	1684		WITH 450 SX CMT
PROD	4.5	7992	2695	WITH 415 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/06/2010 11:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUG PER KCC GUIDELINES AND REGULATIONS WHICH MAY INCLUDE: CIRC HOLE W/MUD. SET 41/2" CIBP @ 5525'. CAP W/2 SKS CMT, CUT & PULL FREE PIPE, MIX AND SPOT 125 SKS CMT @ 1784', MIX AND SPOT 80 SKS CMT 750-510', TOP OUT 64-SURF W/25 SKS CMT, DIG OUT / CUT OFF 4' BGL AND WELD ON ID PLATE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2010 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5502' WITH 5 SX CMT. 1ST PLUG AT 1732' WITH 125 SX CMT. 2ND PLUG AT 692' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 22 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6890	7807		

INVOICED
DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
AUG 11 2010
KCC DODGE CITY

RECEIVED
AUG 19 2010
KCC WICHITA