

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22572-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 12-34S-39W  
4852 feet from S Section Line, 4905 feet from E Section Line  
Lease Name: MID AMERICA CATTLE CO Well #: 12 #1  
County: STEVENS Total Vertical Depth: 6700 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5672		WITH 2 SX CMT
CIBP		6210		
SURF	8.625	1680		WITH 480 SX CMT
PROD	4.5	6690	2131	WITH 520 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2010 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: LOAD CSG W/MUD, CAP EXISTING CIBP @ 6210' W/2 SKS CMT, SET CIBP @ 5680' AND CAP W/2 SKS CMT. SPOT 120 SKS CMT 1730-1287', MIX AND SPOT 50 SKS CMT 675-491', TOP OUT 64-4' W/20 SKS CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2010 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5672' WITH 2 SX CMT. 1ST PLUG AT 1711' WITH 120 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6293	6310		
6272	6290		
5730	5866		

**INVOICED**

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES

Plugged through: TBG

District: 01

RECEIVED  
AUG 17 2010  
KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
AUG 19 2010  
KCC WICHITA

Form CP-28