

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22509-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 34-32S-36W
420 feet from N Section Line, 510 feet from W Section Line
Lease Name: SULLINS Well #: 34 1
County: STEVENS Total Vertical Depth: 6300 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5960		WITH 5 SX CMT
SURF	8.625	1652		350/180 SX CMT.
PROD	5.5	6233	2091	200 SX CMT.

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/15/2010 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUG PER KCC GUIDELINES AND REGULATIONS WHICH MAY INCLUDE: CIRC HOLE W/MUD AND SPOT 4 SKS CMT ON EXISTING CIBP @ 5950, CUT AND PULL FREE PIPE, MIX AND SPOT 100 SKS CMT 1702-1372', MIX AND SPOT 45 SKS CMT 730-570', TOP OUT 54-4' W/ 15 SKS CMT, DIG OUT / CUT OFF 4' BGL AND WELD ON ID PLATE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE
Date/Time Plugging Completed: 09/15/2010 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5960' WITH 5 SX CMT. 1ST PLUG AT 1700' WITH 100 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5988	5996		

INVOICED
DATE _____
INV. NO. _____

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
SEP 22 2010
KCC DODGE CITY

RECEIVED
SEP 30 2010
KCC WICHITA

Form CR-275