

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21876-00-00
Spot: S2SENV Sec/Twnshp/Rge: 13-28S-34W
2997 feet from S Section Line, 3325 feet from E Section Line
Lease Name: VERDA Well #: 13 #1
County: HASKELL Total Vertical Depth: 4800 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3355		WITH 2 SX CMT
CIBP		4131		WITH 2 SX CMT
SURF	8.625	1696		480 SX
PROD	5.5	4786	1726	180 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/30/2010 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: LOAD CSG W/MUD, SET CIBP #2 @ 4136' & CAP W/2 SKS CMT, CUT & PULL FREE PIPE, MIX & SPOT 100 SKS CMT FROM 1795 - 1426', MIX & SPOT 100 SKS CMT FROM 850-500', TOP OUT W/20 SKS CMT FROM 64-4', DIGOUT/CUT OFF 4' BGL & WELD ON ID PLATE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2010 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 3355' WITH 2 SX CMT. CIBP @ 4131' WITH 2 SX CMT. 1ST PLUG AT 1795' WITH 100 SX CMT. 2ND PLUG AT 850' WITH 100 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4643	4648		KANSAS CITY
4404	4409		LANSING
4186	4190		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
OCT - 8 2010
KCC DODGE CITY

Signed

Jack MacLaskey

(TECHNICIAN)

RECEIVED

OCT 14 2010

KCC WICHITA

Form CP-27