

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-00564-00-01  
Spot: SESENW Sec/Twnshp/Rge: 22-34S-36W  
2684 feet from S Section Line, 2740 feet from E Section Line  
Lease Name: BEVAN Well #: 1  
County: STEVENS Total Vertical Depth: 2856 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PKWY P  
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	734		WITH 250 SX CMT
L1	5.5	2856		TOP @ 2654'
PROD	7	2623	0	WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2010 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING REPORT SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/17/2010 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

**\*\*TOP OF FISH @ 1830' (TBG & RODS LEFT IN HOLE) 7" X 10 3/4" ANNULAR HAS CMT TO SURFACE.\*\* PUMP 200# HULLS & 60 SX CMT AT 1830'. SDON. TAGGED TOC @ 1480'. PLUG AT 760' WITH 50 SX CMT. PLUG AT 50' WITH 15 SX CMT.**

Perfs:

Top	Bot	Thru	Comments
2654	2856		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
NOV 18 2010  
KCC DODGE CITY

RECEIVED  
DEC 08 2010

KCC WICHITA