

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-30004-00-01
Spot: NWNE Sec/Twnshp/Rge: 27-24S-17W
4626 feet from S Section Line, 1939 feet from E Section Line
Lease Name: CROSS Well #: 1-27
County: EDWARDS Total Vertical Depth: 4515 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4482		
SURF	8.625	259		WITH 250 SX CMT
PROD	4.5	4514	0	WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/04/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4300' & 4 SX CMT. CUT PIPT AT 1200' & PUMP 70 SX CMT. PERFORATE @ 300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL
Date/Time Plugging Completed: 10/05/2010 3:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4300' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG CUT PIPE @ 1200' & PUMPED 70 SX CMT. PRESSURED TO 750 PSIG. DISPLACED TO 800'. 2ND PLUG PERFORATED @ 300'. PUMPED DOWN 4 1/2" WITH 190 SX CMT CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4414	4418		KINDERHOOK SA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
OCT - 6 2010
KCC DODGE CITY

RECEIVED
OCT 19 2010

KCC WICHITA