

4-031625

12-3

200
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-22,100-00-00

NE SE NW /4 SEC. 24, 13 S, 22 W
3630 feet from S section line
2970 feet from E section line

Operator license# 30160

Lease Rupp well #F-24

Operator: Clute Oil Corporation

County Trego

Address: 444 Seventeenth Street
Suite 608
Denver, Colorado 80202

Well total depth 4150 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet
cwc 160 sx.

134.87

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Drilling Company License# 8241

Address: 4 S. Kansas, P.O. Box 819, Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 3 Month: December Year: 91

Plugging proposal received from: Larry

Company: Emphasis Drilling Phone:

Were: Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. - 8 5/8" W.P.
B.J. Services Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:30 P.M., Day: 3, Month: December, Year: 91

Actual plugging report: Condition bore hole with heavy mud.

Balance plugs with mud. Spot cement plugs with mud.

Spot 25 sx. @ 4105'.

Spot 100 sx. @ 830'.

Spot 40 sx. @ 300' with hulls.

Spot 10 sx. @ 40' with W.P.

Circulate 15 sx. in Rahole with joint of pipe.

RECEIVED
STATE CORPORATION COMMISSION
12-30-91
DEC 30 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elev. 2232' - Anhy. 1665' - Arbuckle 4105'.

INVOICED

I did[] / did not[X] observe the plugging.

Carl Goodrow

Gib. S.

DATE 1-9-92

INV. NO. 34287

(agent)