

6030592

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21,562-00-00

C5W4W, SEC. 7, T. 13 S, R. 23 W

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5639

Lease Name DELANEY Well # 1

Operator: ENERGY EXPLORATION & PROD.
Name & Address: 4700 W 50TH TERRACE #206

County TREGO 144.30

Well Total Depth 4440 feet

SHAWNEE MISSION

Conductor Pipe: Size _____ feet ✓

66201

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 6 Month: 11 Year: 19 85

Plugging proposal received from MARK McCABE

(company name) KELSO CASING. (phone) _____

were: 8 5/8 SET @ 310 W/180 SX. 4 1/2 SET @ 4260 W/125 SX. TOP PERF. 3974

ORDER SAND & COM. CNT. JHoot & RECOVER PIPE ORDER 180 SX.

60/40 PPD 2 GEL 3 HULL 8 5/8 WP 40 SX. GEL. 5 SX. HULLS. ALLIED CNT. CO.

WELLBROCK WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 PM Day: 6 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT DUMP SAND TO 3900 W/4 SX. COM. CNT. W/BANNER. ON TOP

RECOVERED 3003' OF 4 1/2. Pump Down 8 5/8 3 SX. HULLS 30 SX. GEL

100 SX. CNT. MIX. + 2 SX. HULLS 10 SX. GEL 8 5/8 W.P. 100 SX. CNT. MIX.

MAX. PSI 1100 CLOSE IN 300 PLUG. COMPLETE

Remarks: SHOTS @ 3432 3250 3003
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 26 1985

INV. NO. 11219

NOV 20 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

9
11-16-85
mmg