

4- 060365

11-23

183R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-01, 023-00-01

SW NW /4 SEC. 28, 13 S, 24 W
3300 feet from S section line
4620 feet from E section line

Operator license# 30396Lease Fabrizius well # 1Operator: William A. SpiveyCounty TregoAddress: Box 717Hays, Kansas 67601Well total depth 4330 feetConductor Pipe: 0 inch @ 0 feetSurface pipe 8 5/8 Inch @ 265 feetAband. oil well , Gas well , Input well , SWD , D & A XPlugging contractor: Helberg Oil Company License# 5669Address: Morland, KansasCompany to plug at: Hour: 9:00A.M. Day: 23 Month: November Year: 92Plugging proposal received from: Jerry HelbergCompany: Helberg Oil CompanyPhone:

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sack.
Space all plugs with heavy drilling mud thru drill pipe.

Plugging Proposal Received by: Herb DeinesPlugging operations attended by agent? All[], Part[], None[X]Completed: Hour: 11:00A.M. Day: 23 Month: November Year: 92

Actual plugging report:

1st. plug @ 1875' w/25 sx. - Anhydrite 1848' - 1890'.2nd. plug @ 960' w/100 sx. - Dakota 652' - 952'.3rd. plug @ 315' w/40 sx. - Surface pipe to 315'.4th. plug @ 40' w/10 sx.Rathole with 15 sacks.Remarks: Allied Cementing.Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO Plugged through TUBING , CASING . Elevation: 2377 GLI did [] did not [X] observe the plugging.DATE 12-10-92

(agent)

INV. NO. 37063

Form CP-2/3

JAN 22 1993

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1992
12-08-1992
DIVISION
WICHITA, KANSAS

E.A.X.