

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22204-00-00
Spot: E2NESE Sec/Twnshp/Rge: 36-13S-22W
1837 feet from S Section Line, 360 feet from E Section Line
Lease/Unit Name: WEBER Well Number: 3
County: TREGO Total Vertical Depth: 4190 feet

Operator License No.: 32705
Operator Name: RANEY OIL COMPANY, LLC
Address: 3425 TAN O'SHANTER
LAWRENCE, KS 66047

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 247
Production: Size feet:
Liner: Size feet:

136.18

11/12

Well Type: DH UIC Docket No: Date/Time to Plug: 11/12/2000 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HUBERT DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 11/12/2000 11:45 AM KCC Agent: HUBERT DEINES

Actual Plugging Report:

1st. Plug at 1800' w/25 sxs. Anhydrite 1757' - 1805'.
2nd. Plug at 975' w/100 sxs. Dakota 649' - 949'.
3rd. Plug at 300' w/40 sxs. Surface pipe to 247'.
4th Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY. SPOT LOCATION SHOULD READ 143' S. & 30' W. OF E2NESE 36-13-22W.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

INVOICED

DATE 11/27/00

INV. NO. 2001061010

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 2000

CONSERVATION DIVISION
Wichita, Kansas

NOV 13 2000