

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-068-20, 697-00800

4290 feet from N(S) section line

330 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

Lease Name TITTLE Well # 1

Operator: D.N.B. DRILLING, INC.
Name & Address 535 NORTH OLIVER
WICHITA, KANSAS
67208

County GOVE

Well Total Depth 4415 feet 143.49

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor D.N.B. DRILLING License Number 5476

Address 535 NORTH OLIVER, WICHITA, MO. 67208

Company to plug at: Hour: 12:00^{NOON} Day: 18TH Month: NOV. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO JOHN TAYLOR

(company name) D.N.B. DRILLING Co (phone) 216-687-5471

were: 8 5/8" - 297' ^{SK} SP CUL. 1 1/2" ^{SK} COMMUN - 2 1/2" GEL - 3% CA-CL (BY SUN)
ORDER 190 ^{SK} 50/50 Pozmix 6% GEL 3% CA-CL, 1 ^{SK} CELLO FLAME & 8 5/8" Plug
SPOT WITH DRILL STEM-TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUG
NO ARBUCKLE - ELV. 2458, AMH. 1976

Signed *[Signature]*
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:00^{NOON} PM Day: 18TH Month: NOV. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 190 ^{SK} 50/50 Pozmix 6% GEL 3% CA-CL - 8 5/8" Plug - 1 ^{SK} CELLO-FLAME
SPOT WITH DRILL-TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.
1ST Plug @ 1980' ^{SK} 1/20" ENT. - 2ND Plug @ 1200' ^{SK} 1/100" ENT.
1/1 ^{SK} CELLO-FLAME MIXED IN. 3RD Plug @ 300' ^{SK} 1/50" ENT.
4TH Plug ^{SOLID BRIDGE} HULL'S- PLUG @ 40' ^{SK} 1/10" ENT., 10 ^{SK} RAT HOLE (CIRCULATED)

Remarks: CEMENTED BY SUN OMT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION

DATE 12-8-83 NOV 28 1983

INV. NO: 7098-W 11-28-83 CONSERVATION DIVISION Wichita, Kansas

Signed *[Signature]*
(TECHNICIAN) DOIC