

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-195-21, 006-00-00 ✓ R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name RAINS AND WILLIAMSON
Complete Address 435-PAGE COURT - 220th DOUGLAS, WICHITA, KS. 67202
Lease Name HARVEY Well No. #4
Location SW-SE-NE Sec. 16 Twp. 13 Rge. 22 (East)(West)
County TREGO Total Depth 4185 ^{FT}
Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated _____

Plugging Contractor RAINS AND WILLIAMSON (RICH PERFF)
Address 435-PAGE COURT - 220th DOUGLAS, WICHITA, MO. 67202 License No. _____
Operation Completed: Hour: 4:00 AM Day: 29th Month: JULY Year: 1982
Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 217^{FT} SP. CUL^{IN} / 160ST COMMON - 2% GEL - 3% CA-CL.
ORDERED 140ST 50/50 FERRIC 4% GEL - 3% CA-CL. + 8 5/8" PLUG.
SPOTTED WITH DRUG STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG @ 840^{FT} IN / 80ST CMT.
2ND PLUG @ 240^{FT} IN / 40ST CMT.
3RD PLUG → ^{SOLID BRIDGE} HULL'S- PLUG @ 40^{FT} IN / 10ST CMT.
10ST IN RAT HOLE (CIRCULATE)
10ST IN MOUSE HOLE (CIRCULATE)

Amount of Surface Casing: (217) FT

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Mary J. Schmidt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 02 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 8-9-82
NO. 823-W