

15-195-00277-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NE SW

SEC. 25 TWP. 13 RGE. 22

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Pearson

Operator Skelly Oil Co Address Hutchinson, Kans

Field _____ County Trego

Total Depth 4245 Feet.

Plugging Contractor Wentworth Drg Co & Halliburton Cementing

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1275' circulated with cement.

Gunned pits, circulated hole with heavy mud, spotted 25 sax cement

on bottom through drill pipe, heavy mud to 750', set cementing plug,

spotted 35 sax cement through drill pipe at 750', heavy mud to

50', set cementing plug, 1/2 sack hulls and 15 sax cement to 0'.

Cementing by Halliburton Cementing Co.

Edmond L. Perry
District Conservation Agent

Date 5-26-57

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1957
05-28-57
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 25 T. 13 R. 22W
BOOK PAGE 15 LINE 38