

15-195-20259-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 1 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Muhlheim Well No. A-1

Location CNE-NE-SW Sec. 24 Twp. 13 Rge. (E) (W) 22

County Trego Total Depth 4030'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling Company, Incorporated,

Address Above License No. \_\_\_\_\_

Operation Completed: Hour 6:00 AM Day 28 Month 1 Year 1974

The above well was plugged as follows:

235'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 110 Cu. Ft. cement  
thru DP from 750' to 425'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/1/74  
INV. NO. 8494-W

Signed: W. L. Dickel  
Well Plugging Supervisor