

15-195-20233-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1972
08-28-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center, Wichita, Kansas.

Lease Name Ella Well No. 1

Location 150' West of CNE-SE Sec. 11 Twp. 13 Rge. (E) (W)23

County Trego Total Depth 4435'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Thomas Drilling Company, Incorporated,

Address Box #400, Duncan, Oklahoma. License No.

Operation Completed: Hour 2:15 PM Day 25 Month 8 Year 1972

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 735'.

Circulated hole-with heavy mud.- Pulled DP to 960' and displaced 110 Cu. Ft. cement
thru DP from 960' to 635'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. J. Dickels
Well Plugging Supervisor

INVOICED

DATE 8-30-72

INV. NO. 6249-4