

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Trego County. Sec. 27 Twp. 13S. Rge. 22W. (E) W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SW- NE.
Lease Owner Maybrier & Castle
Lease Name Mong Well No. #1
Office Address 1120 Greely, St. Salina, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-28 19.52
Application for plugging filed 1-28 19.52
Application for plugging approved 1-28 19.52
Plugging commenced 1-28 4:00 P.M. 19.52
Plugging completed 1-28 12:00 P.M. 19.52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Soil, shale		0'	148'	8 5/8"	148'	none
Lansing (K.C.)		m3711'	3961'		dry	dry
Arbuckle		4254'	4300'		dry	dry

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred pits well, filled hole with heavy mud to 155'. Set bottom wood plug at 155'. Ran 1/2 sk hulls, and 15 sacks cement on same. Filled hole with heavy mud to 40'. Set wood plug at 40'. Ran 1/2 sks hulls and 10 sacks cement filling to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strain Drilling Company
Address Box 188, Hays, Kansas

01-31-52
JAN 31 1952

STATE OF Kansas, COUNTY OF Ellis, ss.
T.C. Strain (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.C. Strain

Box 188, Hays, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1952.

My commission expires

23-8390-s 6-51-20M

PLUGGING
FILE DEC 27 13 R m-w
BOOK PAGE 141 LINE 37

COMPANY: N.V. Maybrier & J.M. Castle

SW-SW-NE, Sec. 27,
Twp. 13, Rge. 22W,
Trego County, Kansas.

LEASE: Mong #1.

ELEVATION: 2316 Ground Level

NOTE: All meas. rotary Bushings.

0	150 Soil, shale,
150	650 Shale
650	950 Sandy shale
950	1050 Shale, shells
1050	1210 Sand & shale
1210	1380 Shale
1380	1590 Sand
1590	1630 Shale & sand
1630	1880 Redbed
1880	1790 Anhydrite
1790	1825 Anhydrite
1825	2085 Shale & shells
2085	2300 Shale & shells
2300	2420 Shale & lime
2420	2595 Shale & lime
2595	2670 Lime & shale
2670	2760 Lime
2760	2830 Lime & shale
2830	2915 Lime & shale
2915	3050 Lime & shale
3050	3170 Lime & shale
3170	3310 Shale & lime
3310	3390 Shale, redbed, shale
3390	3485 Shale & lime
3485	3570 Shale & lime
3570	3640 Shale & lime
3640	3671 Lime
3671	3685 Lime
3685	3713 Lime
3713	3740 Lime
3740	3798 Lime
3798	3835 Lime
3835	3874 Lime
3874	3907 Lime
3907	3940 Lime
3940	3961 Lime
3961	3990 shale & lime
3990	4050 Shale & ime
4050	4075 Lime & shale

4075	4115 Lime & shale
4115	4156 Shale, lime, chirt
4156	4185 Conglomerate
4185	4228 Conglomerate
4228	4255 Conglomerate
4255	4275 Arbuckle
4275	4300 Arbuckle
4300'	Total Depth (R.B.)

COMMENCED: 1-15-52

COMPLETED: 1-28-52

Casing Record:8 5/8" surface casing set at 148'. w/100
sacks cement by Halliburton.D.S.T. By Halliburton3689-3713'. Tool open 23 min. Recovered
3 Ft. Drilling mud. B.H.P.-10#.

No Electric log Hun.

TOPS:

Anhydrite	1880
Heebner	3676(-1354)
Lansing	3711(-1389)
Marmaton	3961(-1639)

Conglomerate	4163(-1841)
Arbuckle	4254(-1932)
Total Depth	4300'

STATE OF KANSAS) SS
COUNTY OF ELLIS)I hereby affirm that the above and foregoing is a true and correct copy
of the log of the Mong #1, located SW-SW-NE, Sec. 27, twp. 13S, Range. 22W, Trego
County, Kansas.CONTRACTOR: Strain Drilling Company

By

T.C. StrainSubscribed and sworn to before me this 29th day of January, 1952My Commission expires July, 18. 1955.Notary Public
NOTARY PUBLIC