


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

15-195-01511-00-00

WELL PLUGGING RECORD



Trego County, Sec. 26 Twp. 13 Rge. 24 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW
Lease Owner Anschutz Drilling Company
Lease Name Bauer Well No. 1
Office Address 709 Union Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 10 19 51
Application for plugging filed December 10 19 51
Application for plugging approved December 10 19 51
Plugging commenced December 10 19 51
Plugging completed December 10 19 51
Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes
Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation. Depth to top. Bottom. Total Depth of Well. Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		surface	229'	8-5/8	11-21-51	- -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug at 210' and 15 sacks cement
Top Plug at 40' and 10 sacks cement

DEC 19 1951
CONS 12-19-1951
(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.
Address Anschutz Drilling Company
709 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. R. Jensen (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen
709 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of December, 1951.
May 24, 1952
Notary Public.



PLUGGING
FILE SEC. 26-13-11-260
BOOK PAGE 131-11-260

15-195-01511-00-00

ANSCHUTZ DRILLING COMPANY

No. 1 Bauer
NE NE NW 26-13S-24W
Trego County, Kansas

From	To		
0	40	Sand and clay	COMMENCED: 11-21-51
40	530	Shale and Shells	
530	710	Shale	COMPLETED: 12-10-51
710	920	Sand and Shale	
920	1150	Shale, Shells, and Sand	
1150	1350	Shale and Shells	
1350	1650	Sand	
1650	1700	Shale and Shells	
1700	1880	Red Rock	
1880	1931	Anhydrite	
1931	2287	Shale and Shells	
2287	3766	Lime and Shale	
3766	3983	Lime	
3983	4301	Lime and Shale	
4301	4335	Chert	
4335	4367	Chert and Lime	CASING RECORD:
4367	4427	Cherty Lime	
4427	4440	Cherty Lime and Shale	8-5/8" casing set at 229'
4440	4464	Lime	with 200 sacks cement and
4464	4490	Cherty Lime and Shale	200# calcium chloride
4490	4611	Lime and Shale	
4611	4621	Lime, Shale and Chert	
4621	4641	Lime and Chert	
4641	4650	Arbuckle	
4650		TOTAL DEPTH	


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the No. 1 Bauer, located in the NE NE NW Section 26-13S-24W, Trego County, Kansas.

ANSCHUTZ DRILLING COMPANY

H. R. Jensen
H. R. Jensen

Subscribed and sworn to before me this 17th day of December,



DEC 19 1951
WILMA V. SHIPMAN
Notary Public

Wilma V. Shipman
Notary Public

Expires: May 24, 1952

12-19-1951

FILE SEC 26-13-24W
BOOK PAGE 131 LINE 4