


15-195-20339-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 1 Twp. 13S Rge. 24W (E) (W)
Location as "NE/CNW&SW&" or footage from lines C NE NE
Lease Owner John O. Farmer, Inc.
Lease Name Karst #1 Well No.
Office Address Box 352, Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 20, 1975 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced September 20, 1975 19
Plugging completed September 20, 1975 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 850' 70 sx. cement
Plug #2 200' 20 sx. cement
Plug #3 40' 10 sx. cement

Completed 8:30 P.M., 9-20-75
Gilbert Balthazor, State Plugging

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1975
09-29-1975
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor John O. Farmer, Inc.
Address Box 352, Russell, Kansas 67665

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
John O. Farmer (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer
Box 352, Russell, Kansas 67665 (Address)

Subscribed and sworn to before me this 23rd day of September, 1975

My commission expires February 15, 1979
Helen Carlson Notary Public.

KANSAS DRILLERS LOG

API No. 15 — 195 — 20,339-00-00
County Number

Operator
John O. Farmer, Inc.

Address
Box 352, Russell, Kansas 67665

Well No. 1 Lease Name KARST

Footage Location
660 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor John O. Farmer, Inc. Geologist Sam Farmer

Spud Date 9-11-75 Total Depth 4400' P.B.T.D. D & A


Date Completed 9-20-75 Oil Purchaser None - D & A

S. 1 T. 13 R. 24 E W

Loc. C NE NE

County Trego

640 Acres
N



Locate well correctly

Elev.: Gr. 2450'

DF 2453' KB 2455'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½	8-5/8"	26	210	Common	170	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1975
09-29-A75
CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbis.	MCF	bbis.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator John O. Farmer, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name KARST	Dry Hole
S 1 T 13 R 24 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			LOG TOPS:	
Shale & Shells	210	900	Anhydrite	1949' (+506)
Shale & Sand	900	1250	Heebner	3785' (-1330)
Shale	1250	1475	Toronto	3804' (-1349)
Sand	1475	1600	Lansing	3821' (-1366)
Shale & Shells	1600	1890	B/KC	4082' (-1627)
Red Bed	1890	1945	Pawnee	4204' (-1749)
Anhydrite	1945	1991	Cherokee Sh.	4270' (-1815)
Shale & Shells	1991	2485	Cherokee Lime	4278' (-1823)
Shale & Lime	2485	3490	Conglomerate	4350' (-1895)
Lime & Shale	3490	3850	Mississippi	4372' (-1917)
Lime	3850	4400	Log T.D.	4406' (-1951)
Total Depth	4400		Rotary T.D.	4400' (-1945)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div>Signature <i>John O. Farmer</i></div> <div>Title President</div> <div>Date September 23, 1975</div>
---------------	--