

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,965-00-00

LEASE NAME C. J. Weber

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 36 TWP. 13 RGE. 22 XXXXX(W)

COUNTY Trego

Date Well Completed 2-23-88

Plugging Commenced 2-23-88

Plugging Completed 2-23-88

LEASE OPERATOR Nye Exploration Inc.

ADDRESS 3920 East Elm, Suite 4, Wichita, KS 67208

PHONE#(316 685-3920) OPERATORS LICENSE NO. 3506

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-19-88 (date)

by Dave Wann (KCC District Agent's Name).

Is ACO-1 filed? will be by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plug #1 set @ 1610' with 25 sacks cement through drill pipe

Plug #2 set @ 930' with 100 sacks cement through drill pipe

Plug #3 set @ 310' with 40 sacks cement through drill pipe

Plug #4 set @ 40' with 10 sacks cement; 15 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging-Contractor Lobo Drilling Company License No. 5864

Address PO Box 877, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

ERVIN NEIGHBORS (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors


(Address) PO Box 877, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 29 day of February, 19 88

Dorothy M. Maguire
Notary Public

03-03-88
MAR - 3 1988

03-03-88
CONSERVATION DIVISION
Wichita, Kansas



15-195-21965-00-00

DRILLER'S WELL LOG

DATE COMMENCED: February 18, 1988
DATE COMPLETED: February 23, 1988

NYE EXPLORATION INC.
C. J. Weber #1
NW NW SE
Sec. 36, T13S-R22W
Trego County, KS

0 - 40'	Clay with Sand Streaks
40 - 268'	Clay & Shale
268 - 949'	Shales
949 - 980'	Sand
980 - 1030'	Shales
1030 - 1040'	Sand
1040 - 1227'	Shales
1227 - 1468'	Sand
1468 - 1602'	Shales
1602 - 1628'	Shale
1628 - 2494'	Shales & Lime
2494 - 3765'	Lime & Shale
3765 - 4180'	Lime
4180	RTD

ELEVATION: 2334'

Surface Pipe: Set used
8-5/8", 23# pipe @ 266'
with 160 sacks 60/40 poz-
mix, 2% gel, 3% c.c.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 24th day of February, 1988.

RECEIVED
STATE CORPORATION COMMISSION

Dorothy M. Hague
Notary Public

MAR - 3 1988

Wichita, Kansas

