

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Trego County. Sec. 36 Twp. 13 Rge. (E) 22 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE  
Lease Owner Rains & Williamson Oil Co.  
Lease Name Pearson Well No. 1  
Office Address 1425 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-22 1966  
Application for plugging filed 10-22 1966  
Application for plugging approved 10-22 1966  
Plugging commenced 10-22 1966  
Plugging completed 10-22 1966  
Reason for abandonment of well or producing formation no oil or gas found  
in commercial quantities

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Moreland, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4265 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

FORMATION	CONTENT	FROM	TO	SIZE	REMARKS
				8-5/8	233.26

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 540', spot with 20 sx. cement. Mud back to 220', spot with 20 sx. Mud back to 40', set solid bridge and capped with 10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of October, 1966.

My commission expires March 3, 1970

Mary J. Brown  
Notary Public.

15-195-30152-00-00

# ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co. Contractor: Rains & Williamson Oil Co.  
 #1 PEARSON Commenced: 10-12-66  
 NW NW NE Section 36-13S-22W Completed: 10-22-66  
 Trego County, Kansas Remarks: Set 233.26' of used 8-5/8" surface casing with 165 sx. GL3

## FORMATIONS

Clay	45'
Sand	135'
Blue Shale	234'
Shale, Shells & Clay	305'
Shale	1280'
D. Sand	1508'
Red Bed	1794'
Anhydrite	1839'
Red Bed & Shale	2065'
Shale & Lime	2495'
Lime w/Shale	2634'
Lime & Shale	2754'
Lime	2838'
Shale w/Lime	3075'
Lime & Shale	3645'
Lime	3995'
Lime & Congl. Sh.	4105'
Lime & Chert	4215'
Chert	4249'
Lime & Chert	4265'

Rotary Total Depth 4265'

RECEIVED  
STATE CORPORATION COMMISSION

OCT 25 1966

CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true  
and correct to the best of our  
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains

Subscribed and sworn to before me, a Notary Public, in and for the State of  
Kansas, County of Sedgwick, this 24th day of October, 1966.

My Commission Expires: 3-3-70

*Mary J. Brown*  
Mary J. Brown, Notary Public