

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-063-20873-00-00

API NUMBER 15-063-20,783-00-00

LEASE NAME Walz

WELL NUMBER 1

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 15 TWP. 13S RGE. 26 ~~XXXX~~ (W)

COUNTY Gove

Date Well Completed 1-26-85

Plugging Commenced 1-26-85

Plugging Completed 1-26-85

LEASE OPERATOR Sandlin Oil Corporation

ADDRESS 2300 Security Life Bldg., Denver, CO 80202

PHONE# (303) 623-5055 OPERATORS LICENSE NO. 6677

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4435' RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	260'	8 5/8"	260'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4439' - 2050' 10 sks cement @ 40'
20 sks cement @ 2050' 10 sks cement @ Rathole
100 sks cement @ 1040' 10 sks cement @ Mousehole
40 sks cement @ 300'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1985

Joe K. Branum (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe K. Branum

(Address) P.O. Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 85

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS

My Appointment Expires: 2-13-85 My Commission Expires: _____

Denise S. Reynolds
Denise S. Reynolds, Notary Public
2-13-85

15-063-20873-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Sandlin Oil Corporation
2300 Security Life Bldg.
Denver, CO 80202

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506,
Russell, KS 67665

LEASE: Walz WELL: #1

LOCATION: NW SE NW
Section 15-13S-26W
Gove County, Kansas

ROTARY TOTAL DEPTH: 4435'

LOG TOTAL DEPTH: 4439'

ELEVATION: 2465' K.B.

COMMENCED: 1-18-85

DATE COMPLETED: 1-26-85

CASING: 8 5/8" @ 260' with 160 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	30'	Shale	2245'
Sand & Shale	1428'	Shale & Shells	2736'
Shale	1590'	Shale	2900'
Sand	1770'	Shale & Lime	3277'
Shale & Sand	2024'	Shale	3419'
Anhydrite	2068'	Shale & Lime	4140'
Shale	2087'	Lime	4210'
Shale & Shells	2165'	Lime & Shale (RTD)	4435'

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Joe K. Branum

RECEIVED
STATE CORPORATION COMMISSION


Subscribed and sworn to before me this 28th day of January, 1985.

My Commission Expires: February 13, 1985.

JAN 29 1985

CONSERVATION DIVISION
Wichita, Kansas

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-13-85


Denise S. Reynolds, Notary Public