



15-195-20142-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
11-03-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Chas Keevert of Birmingham-Bartlett Drlg. Co. has this  
date requested permission to plug the following described well:

Mr. Keevert guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Company,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name: Karst Well No. 1

Location: NE-SW-SE, Sec. 1 Twp. 13 Rge. (E)(W) 24

County: Trego Total Depth 4525 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Keevert was instructed to plug the well as follows:

287'--8 5/8" Surface casing, cement circulated with 215 Sx.  
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack bulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*M. J. Nichols*

Conservation Division Agent