

State of Kansas



15-063-20027-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman-Iannitti Drlg. Co., has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti Drilling Company,

Complete Address: 706 Union National Bank Building, Wichita, Kansas.

Lease Name: Blackwell Well No. 1

Location: CSE-SE Sec. 8 Twp. 13 Rge. (E)(W) 26

County: Gove Total Depth 4530 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

20 1/2" - 8 5/8" Surface pipe, cement circulated with 130 Sx.
Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

JUL 1 1968

CONSERVATION DIVISION
Wichita, Kansas

W. L. Nichols
Conservation Division Agent