

Amended



KANSAS CORPORATION COMMISSION 1055718  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
June 2009

Form Must Be Typed  
Form must be Signed  
All blanks must be Filled

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 33739  
Name: SEK Energy, LLC  
Address 1: 149 BENEDICT RD  
Address 2: PO BOX 55  
City: BENEDICT State: KS Zip: 66714 +  
Contact Person: Kerry King  
Phone: ( 620 ) 698-2150  
CONTRACTOR: License # 33606  
Name: Thornton Air Rotary, LLC  
Wellsite Geologist: Julie Shaffer  
Purchaser:

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  WSW  SWD  SIOW  
 Gas  D&A  ENHR  SIGW  
 OG  GSW  Temp. Abd.  
 CM (Coal Bed Methane)  
 Cathodic  Other (Core, Expl., etc.):

If Workover/Re-entry: Old Well Info as follows:  
Operator:  
Well Name:  
Original Comp. Date: Original Total Depth:  
 Deepening  Re-perf.  Conv. to ENHR  Conv. to SWD  
 Conv. to GSW  
 Plug Back: Plug Back Total Depth  
 Commingled Permit #:  
 Dual Completion Permit #:  
 SWD Permit #:  
 ENHR Permit #:  
 GSW Permit #:  
01/04/2007 01/05/2007 01/15/2008  
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 15-205-27049-00-00  
Spot Description:  
NW NE NE NE Sec. 20 Twp. 29 S. R. 16  East  West  
30 Feet from  North /  South Line of Section  
360 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Wilson  
Lease Name: BURKEY ESTES Well #: 1-20  
Field Name:  
Producing Formation: Cherokee Basin CBM  
Elevation: Ground: 817 Kelly Bushing: 0  
Total Depth: 1088 Plug Back Total Depth: 938  
Amount of Surface Pipe Set and Cemented at: 44 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set: Feet  
If Alternate II completion, cement circulated from: 938  
feet depth to: 0 w/ 105 sx cmt.

Drilling Fluid Management Plan  
(Data must be collected from the Reserve Pit)  
Chloride content: 0 ppm Fluid volume: 0 bbls  
Dewatering method used: Evaporated  
Location of fluid disposal if hauled offsite:  
Operator Name:  
Lease Name: License #:  
Quarter Sec. Twp. S. R.  East  West  
County: Permit #:

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Submitted Electronically

KCC Office Use ONLY

Letter of Confidentiality Received  
Date: 05/13/2011  
 Confidential Release Date:  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution  
ALT  I  II  III Approved by: Deanna Garrison Date: 05/16/2011



1055718

Operator Name: SEK Energy, LLC Lease Name: BURKEY ESTES Well #: 1-20  
 Sec. 20 Twp. 29 S. R. 16  East  West County: Wilson

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No  Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Submitted Electronically <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(If no, Submit Copy)</i>  List All E. Logs Run: <b>Attached</b>	<input checked="" type="checkbox"/> Log    Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Name</th> <th style="text-align: left;">Top</th> <th style="text-align: left;">Datum</th> </tr> </thead> <tbody> <tr> <td>Lenapah Lime</td> <td>403</td> <td>+407</td> </tr> <tr> <td>Altamont Lime</td> <td>442</td> <td>+368</td> </tr> <tr> <td>Pawnee Lime</td> <td>546.5</td> <td>+263.5</td> </tr> <tr> <td>Oswego Lime</td> <td>623</td> <td>+187</td> </tr> <tr> <td>Verdigris Lime</td> <td>742</td> <td>+68</td> </tr> <tr> <td>Mississippi</td> <td>1044.5</td> <td>-234.5</td> </tr> </tbody> </table>	Name	Top	Datum	Lenapah Lime	403	+407	Altamont Lime	442	+368	Pawnee Lime	546.5	+263.5	Oswego Lime	623	+187	Verdigris Lime	742	+68	Mississippi	1044.5	-234.5
Name	Top	Datum																				
Lenapah Lime	403	+407																				
Altamont Lime	442	+368																				
Pawnee Lime	546.5	+263.5																				
Oswego Lime	623	+187																				
Verdigris Lime	742	+68																				
Mississippi	1044.5	-234.5																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11	8.625	18	44	Class A	35	
Production	6.75	4.5	10.5	938	Thickset	105	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD	-			
___ Plug Off Zone	-			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4	17 Shots at 650-654'	400gal 15%HCl, 533 bbls water,	650-654'
4	17 Shots at 668-672'	50 ballsealers, 9300# sand	668-672'

TUBING RECORD: Size: <u>2 3/8"</u> Set At: <u>729'</u> Packer At: <u>n/a</u> Liner Run: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Date of First, Resumed Production, SWD or ENHR: <u>01/15/2008</u>	Producing Method: <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other <i>(Explain)</i> _____
Estimated Production Per 24 Hours	Oil Bbls. <u>0</u> Gas Mcf <u>30</u> Water Bbls. <u>20</u> Gas-Oil Ratio _____ Gravity _____

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input checked="" type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <i>(Submit ACO-5)</i> <i>(Submit ACO-4)</i> <input type="checkbox"/> Other <i>(Specify)</i> _____	PRODUCTION INTERVAL: _____ _____
--	---	--

Form	ACO1 - Well Completion
Operator	SEK Energy, LLC
Well Name	BURKEY ESTES 1-20
Doc ID	1055718

All Electric Logs Run

Den-Neu Log
DIL Log
Temp Log
Radioactivity Log

Conservation Division  
Finney State Office Building  
130 S. Market, Rm. 2078  
Wichita, KS 67202-3802



phone: 316-337-6200  
fax: 316-337-6211  
<http://kcc.ks.gov/>

Thomas E. Wright, Chairman  
Ward Loyd, Commissioner

Corporation Commission

Sam Brownback, Governor

May 13, 2011

Kerry King  
SEK Energy, LLC  
149 BENEDICT RD  
PO BOX 55  
BENEDICT, KS 66714

Re: ACO1  
API 15-205-27049-00-00  
BURKEY ESTES 1-20  
NE/4 Sec.20-29S-16E  
Wilson County, Kansas

Dear Production Department:

We are herewith requesting that the Well Completion Form ACO-1 and attached information for the subject well be held confidential for a period of two years.

Should you have any questions or need additional information regarding subject well, please contact our office.

Respectfully,  
Kerry King

Conservation Division  
Finney State Office Building  
130 S. Market, Rm. 2078  
Wichita, KS 67202-3802



phone: 316-337-6200  
fax: 316-337-6211  
<http://kcc.ks.gov/>

Thomas E. Wright, Chairman  
Ward Loyd, Commissioner

Corporation Commission

Sam Brownback, Governor

May 16, 2011

Kerry King  
SEK Energy, LLC  
149 BENEDICT RD  
PO BOX 55  
BENEDICT, KS 66714

Re: ACO-1  
API 15-205-27049-00-00  
BURKEY ESTES 1-20  
NE/4 Sec.20-29S-16E  
Wilson County, Kansas

Dear Kerry King:

K.A.R. 82-3-107 provides for all completion information to be filed within 120 days of the spud date. Subsection(e)(2) of that regulation states "All rights to confidentiality shall be lost if the filings are not timely."

The above referenced well was spudded on 01/04/2007 and the ACO-1 was received on May 13, 2011 (not within the 120 days timely requirement).

Therefore, your request for confidential treatment of data contained within the ACO-1 filing cannot be granted at this time.

If you should have any questions, please do not hesitate to contact me at (316)337-6200.

Sincerely,

Production Department