

Amended



KANSAS CORPORATION COMMISSION 1055744
OIL & GAS CONSERVATION DIVISION

Form ACO-1
June 2009

Form Must Be Typed
Form must be Signed
All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 33739
Name: SEK Energy, LLC
Address 1: 149 BENEDICT RD
Address 2: PO BOX 55
City: BENEDICT State: KS Zip: 66714
Contact Person: Kerry King
Phone: (620) 698-2150
CONTRACTOR: License # 33739
Name: SEK Energy, LLC
Wellsite Geologist: Julie Shaffer
Purchaser:

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil WSW SWD SLOW
 Gas D&A ENHR SIGW
 OG GSW Temp. Abd.
 CM (Coal Bed Methane)
 Cathodic Other (Core, Expl., etc.):

If Workover/Re-entry: Old Well Info as follows:
Operator:
Well Name:
Original Comp. Date: Original Total Depth:
 Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW
 Plug Back: Plug Back Total Depth
 Commingled Permit #:
 Dual Completion Permit #:
 SWD Permit #:
 ENHR Permit #:
 GSW Permit #:
09/12/2006 09/13/2006 06/06/2007
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 15-205-26926-00-00
Spot Description:
NE_SW_NW_SW Sec. 17 Twp. 29 S. R. 16 East West
1,680 Feet from North / South Line of Section
335 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Wilson
Lease Name: GANN SCOTT E Well #: 1-17
Field Name:
Producing Formation: Cherokee Basin CBM
Elevation: Ground: 931 Kelly Bushing: 0
Total Depth: 1247 Plug Back Total Depth: 1240
Amount of Surface Pipe Set and Cemented at: 22 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set: Feet
If Alternate II completion, cement circulated from: 1240
feet depth to: 0 w/ 180 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content: 0 ppm Fluid volume: 0 bbls
Dewatering method used: Evaporated
Location of fluid disposal if hauled offsite:
Operator Name:
Lease Name: License #:
Quarter Sec. Twp. S. R. East West
County: Permit #:

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Submitted Electronically

KCC Office Use ONLY

Letter of Confidentiality Received
Date: 05/13/2011
 Confidential Release Date:
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
ALT I II III Approved by: Deanna Garrison Date: 05/16/2011



1055744

Operator Name: SEK Energy, LLC Lease Name: GANN SCOTT E Well #: 1-17
 Sec. 17 Twp. 29 S. R. 16 East West County: Wilson

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Submitted Electronically <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(If no, Submit Copy)</i> List All E. Logs Run: Attached	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Name</th> <th style="text-align: left;">Top</th> <th style="text-align: left;">Datum</th> </tr> </thead> <tbody> <tr> <td>Lenapah Lime</td> <td>562</td> <td>+373</td> </tr> <tr> <td>Altamont Lime</td> <td>600</td> <td>+335</td> </tr> <tr> <td>Pawnee Lime</td> <td>717</td> <td>+218</td> </tr> <tr> <td>Oswego Lime</td> <td>788.25</td> <td>+146.75</td> </tr> <tr> <td>Verdigris Lime</td> <td>907.5</td> <td>+27.5</td> </tr> <tr> <td>Mississippi</td> <td>1195</td> <td>-206</td> </tr> </tbody> </table>	Name	Top	Datum	Lenapah Lime	562	+373	Altamont Lime	600	+335	Pawnee Lime	717	+218	Oswego Lime	788.25	+146.75	Verdigris Lime	907.5	+27.5	Mississippi	1195	-206
Name	Top	Datum																				
Lenapah Lime	562	+373																				
Altamont Lime	600	+335																				
Pawnee Lime	717	+218																				
Oswego Lime	788.25	+146.75																				
Verdigris Lime	907.5	+27.5																				
Mississippi	1195	-206																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11	8.625	18	22.5	Portland	6	
Production	6.75	4.5	10.5	1240	OWC	180	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD	-			
___ Plug Off Zone	-			

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4	13 Shots at 815-818'	400gal 15%HCl, 225bbls water,	815-818'
4	17 Shots at 830-834'	2700# Sand, 45 ballsealers	930-834'

TUBING RECORD: Size: <u>2 3/8"</u> Set At: <u>954.15'</u> Packer At: <u>n/a</u>		Liner Run: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Date of First, Resumed Production, SWD or ENHR. <u>06/06/2007</u>		Producing Method: <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain) _____	
Estimated Production Per 24 Hours	Oil Bbls. <u>0</u>	Gas Mcf <u>30</u>	Water Bbls. <u>20</u> Gas-Oil Ratio _____ Gravity _____

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input checked="" type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <i>(Submit ACO-5)</i> <i>(Submit ACO-4)</i> <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: _____ _____
--	--	--

Form	ACO1 - Well Completion
Operator	SEK Energy, LLC
Well Name	GANN SCOTT E 1-17
Doc ID	1055744

All Electric Logs Run

Den-Neu Log
DIL Log
Temp Log
Radioactivity Log

Conservation Division
Finney State Office Building
130 S. Market, Rm. 2078
Wichita, KS 67202-3802



phone: 316-337-6200
fax: 316-337-6211
<http://kcc.ks.gov/>

Thomas E. Wright, Chairman
Ward Loyd, Commissioner

Corporation Commission

Sam Brownback, Governor

May 13, 2011

Kerry King
SEK Energy, LLC
149 BENEDICT RD
PO BOX 55
BENEDICT, KS 66714

Re: ACO1
API 15-205-26926-00-00
GANN SCOTT E 1-17
SW/4 Sec. 17-29S-16E
Wilson County, Kansas

Dear Production Department:

We are herewith requesting that the Well Completion Form ACO-1 and attached information for the subject well be held confidential for a period of two years.

Should you have any questions or need additional information regarding subject well, please contact our office.

Respectfully,
Kerry King

Conservation Division
Finney State Office Building
130 S. Market, Rm. 2078
Wichita, KS 67202-3802



phone: 316-337-6200
fax: 316-337-6211
<http://kcc.ks.gov/>

Thomas E. Wright, Chairman
Ward Loyd, Commissioner

Corporation Commission

Sam Brownback, Governor

May 16, 2011

Kerry King
SEK Energy, LLC
149 BENEDICT RD
PO BOX 55
BENEDICT, KS 66714

Re: ACO-1
API 15-205-26926-00-00
GANN SCOTT E 1-17
SW/4 Sec. 17-29S-16E
Wilson County, Kansas

Dear Kerry King:

K.A.R. 82-3-107 provides for all completion information to be filed within 120 days of the spud date. Subsection(e)(2) of that regulation states "All rights to confidentiality shall be lost if the filings are not timely."

The above referenced well was spudded on 09/12/2006 and the ACO-1 was received on May 13, 2011 (not within the 120 days timely requirement).

Therefore, your request for confidential treatment of data contained within the ACO-1 filing cannot be granted at this time.

If you should have any questions, please do not hesitate to contact me at (316)337-6200.

Sincerely,

Production Department