

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00447-00-01
Spot: E2NESE Sec/Twnshp/Rge: 17-8S-25W
1980 feet from S Section Line, 330 feet from E Section Line
Lease Name: MADDEN-DAVIS 'B' Well #: 1
County: GRAHAM Total Vertical Depth: 1450 feet

Operator License No.: 34515
Op Name: 6G TWISTER, INC.
Address: PO BOX 1686
GILLETTE, WY 82717

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	199	0	w/unknown sxs cmt
PROD	5.5	3797	0	w/unknown sxs cmt

Well Type: OG UIC Docket No: Date/Time to Plug: 04/29/2011 1:30 PM
Plug Co. License No.: 34514 Plug Co. Name: GREENE ENTERPRISES OF KANSAS, INC.
Proposal Rcvd. from: LEE GREENE Company: 6G TWISTER, INC. Phone: (307) 682-7360

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel - 200# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2011 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

8 5/8" surface casing set at 199' w/ unknown sxs cement.
5 1/2" production casing set at 3797' w/unknown sxs cement.
TD 3805'. Well plugged on 02/02/1966 with 105 sxs cement - 1450' of 5 1/2" production casing pulled - lease owner was Empire Drilling Company.
Well washed down to 1450' - bit outside of pipe - operator decision to plug.
Filled hole with heavy mud - ran tubing to 1450' - pumped 100 sxs cement.
Pulled tubing to 250' - pumped 40 sxs cement.
Pulled tubing to 40' - pumped 10 sxs cement.
Pumped 10 sxs cement - plug complete.

Remarks: ALLIED CEMENTING COMPANY-TICKET #039924.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

RECEIVED

MAY 09 2011

Form CP-2/3

KCC WICHITA

MAY 02 2011