

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23623-00-00  
Spot: NENESE Sec/Twnshp/Rge: 25-16S-22W  
2311 feet from S Section Line, 327 feet from E Section Line  
Lease Name: KRESSIN Well #: 3  
County: NESS Total Vertical Depth: 4360 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4230		WITH 3 SX CMT
SURF	8.625	203		WITH 125 SX CMT
DVT		1701		WITH 250 SX CMT
PROD	5.5	4359	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/02/2011 11:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed Plugging Method: RUN CIBP & 3 SX CMT. RUN TBG TO 1700' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/02/2011 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4150' & 3 SX CMT. RUN TBG TO 1709' & PUMP 165 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4289	4292		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR & FAILED CASING TEST\*\*USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

MAY - 5 2011

KCC DODGE CITY

Signed

*Michael Maier*  
(TECHNICIAN)

RECEIVED

MAY 09 2011

KCC WICHITA

Form CP-23