

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23331-00-00
Spot: SENESE Sec/Twnshp/Rge: 25-16S-22W
1633 feet from S Section Line, 328 feet from E Section Line
Lease Name: KRESSIN Well #: 1
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4150		WITH 3 SX CMT
SURF	8.625	211		WITH 130 SX CMT
DVT		1660		WITH 400 SX CMT
PROD	4.5	4405	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2011 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES Phone: (620) 793-2146

Proposed Plugging Method: SET CIBP & 3 SX CMT. RUN TBG TO 1700' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/02/2011 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4150' & 3 SX CMT. RAN TBG TO 1709' & PUMPED 165 SX CMT. DID NOT CIRCULATE. LOST CIRCULATION. PULLED TBG & WAITED 4 HOURS. SHOT A FLUID LEVEL. FOUND CMT AT 1200'. PUT SWEDGE ON CASING & PUMPED 60 SX CMT. PRESSURED TO 500#. TIED ONTO BACKSIDE & PRESSURED UP TO 500#.

Perfs:

Top	Bot	Thru	Comments
4322	4326		

Remarks: **COMPLIANCE ISSUE: DENIED TA: 10 YR & FAILED CASING TEST** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
MAY -5 2011
KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

RECEIVED
MAY 09 2011
KCC WICHITA