

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22726-00-00
Spot: SESESE Sec/Twnshp/Rge: 23-11S-16W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: BOWLBY Well #: 1-23
County: ELLIS Total Vertical Depth: 3400 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	w/unknown sxs cmt
PROD	4.5	0	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2011 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
CIBP at 2989'. PBDT 3320'.
Log Tech perfed at 1500' - 940' - 475'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2011 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2957'.
Swift Cementing rigged to tubing and pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1510' - pumped 180 sxs cement with 200#hulls mixed in to circulate cement up 4 1/2" casing and out of 8 5/8" casing.
Pulled tubing. Shut in 8 5/8" casing - placed a swedge on 4 1/2" casing and pressured 4 1/2" and 8 5/8" casing with 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3325	3327		

Remarks: SWIFT CEMENTING SERVICES-TICKET #19485.
Plugged through: TBG

RECEIVED
MAY 09 2011
KCC WICHITA

District: 04

Signed [Signature]
(TECHNICIAN) CM

APR 29 2011