

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20332-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 33-9S-25W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BRUNGARDT A Well #: 1  
County: GRAHAM Total Vertical Depth: 4028 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209	0	w/170 sxs cmt
PROD	5.5	4019	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2011 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JODY SMITH Company: AMERICAN WARRIOR, INC Phone: (620) 272-1023

Proposed Plugging Method: Ordered 475 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Shot tubing off at 3780'.  
Perforated at 2190' - 1350' - 195'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/25/2011 12:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3757' - pumped 25 sxs 60/40 pozmix - 4% gel - followed with 150 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 2200' - pumped 85 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1350' - pumped 135 sxs 60/40 pozmix - 4% gel to circulated to surface.  
Pulled all tubing. Hooked to 5 1/2" casing - pumped 80 sxs 60/40 pozmix - 4% gel to circulate out of 8 5/8" x 5 1/2" annulus.  
Shut annulus and pressured 5 1/2" casing to S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3957	3961		
3839	3842		

RECEIVED  
MAY 02 2011  
KCC WICHITA

Remarks: SWIFT SERVICERS, INC.-TICKET #19483.

Plugged through: TBG

District: 04

Signed

Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

APR 27 2011