

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-03004-00-00  
Spot: E2NESWNE Sec/Twnshp/Rge: 25-14S-15W  
3630 feet from S Section Line, 1485 feet from E Section Line  
Lease Name: EHRlich C Well #: 2  
County: RUSSELL Total Vertical Depth: 3190 feet

Operator License No.: 6246  
Op Name: BENNETT & SCHULTE OIL CO., A GEN  
Address: 140 W WICHITA AVE  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	638	0	w/350 sxs cmt
PROD	5.5	3187	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2011 12:30 PM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: E. MICHAELIS Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 483-2721

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls - 10 sxs gel.  
Perf: 650' - 1500'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/22/2011 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2970' - pumped 10 sxs gel - followed with 50 sxs cement with 200# hulls.  
Pulled tubing to 1500' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 610' - pumped 90 sxs cement - cement circulated.  
POOH. Topped off with 5 sxs cement.  
Hooked up to Braden head. Max. P.S.I. 400#.

Perfs:

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #4989.

Plugged through: TBG

RECEIVED  
MAY 02 2011  
KCC WICHITA

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN) CM