

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03291-00-00
Spot: N2SENV Sec/Twnshp/Rge: 16-15S-13W
3960 feet from S Section Line, 3300 feet from E Section Line
Lease Name: HOLLAND CO. Well #: 2
County: RUSSELL Total Vertical Depth: 3149 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	200	0	110 SX
PROD	5.5	3064	0	145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2011 9:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perf: 900' - 495'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2011 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3115' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 2113' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1110' - pumped 150 sxs cement with 200# hulls - cement circulated.
POOH. Hooked on casing and pumped 40 sxs cement with 150# P.S.I.
Hooked up to Braden head and pumped 35 sxs cement. P.S.I. 100#.
The weld on casing started to leak.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TIKET #39684.

Plugged through: TBG

RECEIVED
MAY 02 2011
KCC WICHITA

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

APR 25 2011