

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20086-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 32-16S-19W  
1115 feet from N Section Line, 1520 feet from W Section Line  
Lease Name: SCHMIDT A Well #: 6  
County: RUSH Total Vertical Depth: 3819 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	148		WITH 135 SX CMT
DVT		1270		WITH 450 SX CMT TO 10'
PROD	4.5	3790	0	WITH 525 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/29/2011 10:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: RUN TBG TO 3700' & PUMP 10 SX GEL & 50 SX CMT. PULL TBG TO 1400' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2011 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

**\*\*JUNK IN HOLE @ 3710\*\*** RUN TBG TO 3677' & PUMP 10 SX GEL - 500# HULLS & 50 SX CMT. PULLED TBG TO 1290' & PUMPED 125 SX CMT. CMT DID NOT CIRCULATE & HAD NO LIFT PRESSURE. PULLED TBG & CMT WAS AT 1000'. WILL COME BACK & TOP OFF. TIED ONTO BACKSIDE & PRESSURE TO 500#. 5/4/11: RUN WIRE LINE IN & FOUND CMT AT 1230'. FLUID WAS AT 10' COULDN'T PUMP IN TO. RUN TBG TO 1200' & PUMPED 60 SX CMT & 300# HULLS. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 10 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3790	3819	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Michael Maier*  
(TECHNICIAN)

RECEIVED

MAY - 5 2011

KCC DODGE CITY

RECEIVED

MAY 09 2011

KCC WICHITA

Form CP-2/3