

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19210-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 9-27S-6E
4990 feet from S Section Line, 1291 feet from E Section Line
Lease Name: MCGINNIS Well #: 13
County: BUTLER Total Vertical Depth: 3135 feet

Operator License No.: 6407
Op Name: FLOWERS PRODUCTION CO., INC.
Address: PO BOX 249
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 5		3130		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2011 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO., INC. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/11/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-7-2011, TAG BOTTOM @ 3100', FLUID LEVEL @ 120'. DUMP 30 GAL SAND. 4-8-2011, TAG BOTTOM @ 3075', DUMP BAILED 5 SXS CEMENT ON TOP @ 3075'. 4-11-2011, LOADED HOLE TO SURFACE & SHOT SQUEEZE HOLES FROM 250'-251'. 4-11-2011, SWEDGED INTO 5-1/2" CASING & ESTABLISHED CIRCULATION, CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 335 SXS 60/40 POZMIX 4% GEL, 1% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-11-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #30861.

Perfs:

Top	Bot	Thru	Comments
3130	3135	OH	OPEN HOLE

RECEIVED
MAY 19 2011
KCC WICHITA

Remarks: 10 YEAR TA

Plugged through: TBG

District: 02

Signed _____

Duane Krueger
(TECHNICIAN)

JK