

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20127-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 16-21S-13W
4297 feet from S Section Line, 2321 feet from E Section Line
Lease Name: HARMS Well #: 3
County: STAFFORD Total Vertical Depth: 3629 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	358		WITH 265 SX CMT
PROD	5.5	3628	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2011 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: TOP OF TBG FISH @ 1920' ATTEMPTED TO FISH WITH NO SUCCESS. RUN TBG TO 1900' & SPOT 50 SX CMT WITH 100# HULLS MIXED IN. PERFORATE 5 1/2" @ 790'. RUN TBG TO 800' & CIRCULATE CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2011 3:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 1860' & PUMPED 50 SX CMT WITH 100# HULLS MIXED IN. PULLED TBG TO 800'. PUMPED 250 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2" AND 8 5/8" X 5 1/2" ANNULUS. RAN OUT OF CMT. PULLED TBG OUT OF HOLE & TOPEED OFF WITH READY MIX.

Perfs:

Top	Bot	Thru	Comments
3615	3624		
3558	3566		
3464	3469		

Remarks: USED 60/40 POZMIX 4% BY COPELAND ACID.

Plugged through: TBG

RECEIVED
MAY 16 2011
KCC WICHITA

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAY 13 2011
KCC DODGE CITY