

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20020-00-01
Spot: NWSENESE Sec/Twnshp/Rge: 19-14S-10W
1664 feet from S Section Line, 411 feet from E Section Line
Lease Name: BORELL A Well #: 2
County: ELLSWORTH Total Vertical Depth: 2878 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240		150 SX
PROD	5.5	2877		75 SX

(Well Type: EOR UIC Docket No: E18315.9 Date/Time to Plug: 04/27/2011 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW. NO PERFS OR MENTION OF CASING LEAK ON CP-1. JEFF KLOCK OBTAINED THE PERFS AND HAND WROTE THEM ON CP-1 IN DIST 2 CP-1 FILE.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/27/2011 1:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, THIS WELL HAD PREVIOUSLY BEEN SANDED OVER PERFS TO MIT CASING. CAPPED SAND WITH 5 SX'S CEMENT. PERFORATE AT 1200', 850', AND 290'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT 3% CC AND COTTON HULLS, PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT WITH 3% CC AND COTTON HULLS. PULL TUBING UP TO 290' AND LET CEMENT SET UP. TAGGED CEMENT AT 550'. CIRCULATE CEMENT FROM 290' TO SURFACE. PULL TUBING OUT AND TOP OFF. SURFACE CASING WAS FULL OF HARD CEMENT.

Top	Bot	Thru	Comments
2816	2820	CSG	

Remarks: 60-40 POZ, 4% GEL. PIONEER WIRELINE #33309. QUALITY TICKET #5185.

Plugged through: TBG

RECEIVED

MAY 17 2011

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

KCC WICHITA

JK

cc: JIC
5/18/11