

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20686-00-00
Spot: SENWSENE Sec/Twnshp/Rge: 20-14S-10W
3565 feet from S Section Line, 705 feet from E Section Line
Lease Name: PEKAREK Well #: 7
County: ELLSWORTH Total Vertical Depth: 2930 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	254		170 SX
PROD	4.5	2928		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW. NO PERFS OR MENTION OF CASING LEAK OR JUNK IN HOLE ON CP-1.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/29/2011 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU ON 4-28-11, RICHARD MCINTYRE HAD BEEN INFORMED THAT THERE WAS 26 JTS OF TUBING WITH AD-1 PACKER STUCK IN HOLE AT 820'. EFFORT WAS MADE TO PULL TUBING AND PACKER OUT--PULLED UP 2 JTS--GOT STUCK AGAIN, POSSIBLY IN A CASING LEAK. SHOVED PACKER ON DOWN TO BOTTOM OF HOLE AND UNSCREWED OFF--PULLED TUBING ON OUT. RUN TUBING TO NEAR BOTTOM AND PUMPED 40 SX'S CEMENT WITH 3% CC AND COTTON HULLS. PULL TUBING OUT. PERFORATE ON 4-29-2011 AT 1200', 850' AND 305'. RUN TUBING TO 1200' AND PUMPED 35 SX'S CEMENT WITH 3% CC AND 100#'S COTON HULLS. PULL TUBING TO 850' AND PUMP 35 SX'S CEMENT WITH 3% CC AND 100#'S COTON HULLS. PULL TUBING UP TO 305' AND WAIT AWHILE TO TAG WITH WIRELINE. TAGGED CEMENT AT 400'. CIRCULATE CEMENT FROM 305' TO SURFACE OUT OF BOTH CASINGS. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2903	2915	CSG	
2891	2894	CSG	
2828	2844	CSG	
2448	2453	CSG	
2115	2119	CSG	
2090	2095	CSG	

Remarks: 60-40 POZ, 4% GEL. PIONEER WIRELINE #34004. QUALITY TICKET #5187.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED

MAY 17 2011

KCC WICHITA

JK